BRUHATH BANGALORE MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P.Bengaluru-64

Original/Duplicate

APPROVED SCHEDULE-'B'

NAME OF THE WORK : Improvements of Rcc Drain and CC Roads to Cross Roads at Basavalingappa Layout and Surrounding areas in Ward No.03

SI	Description	Unit	Approved Quantity	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3.	Cum	1180.49	220.40	Rupees Two Hundred Twenty And Paise Forty Only
2	Removing And Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	276.50	111.30	Rupees One Hundred Eleven And Paise Thirty Only
3	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	214.23	5421.90	Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only
4	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm	Cum	344.17	7070.20	Rupees Seven Thousand Seventy And Paise Twenty Only

Signature Of The Contractor

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Yelahanka Division

Sl	Description	Unit	Approved Quantity	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate In Words
5	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, for coping. Including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	30.36	5599.98	Rupees Five Thousand Five Hundred Ninety Nine And Paise Ninety Eight Only
6	Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.Specification No. KBS 4.6.3. TMT Bars Fe 550	Tonne	26.68	72326.98	Rupees Seventy Two Thousand Three Hundred Twenty Six And Paise Ninety Eight Only
7	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	585.70	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
8	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 25cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	61.26	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
9	Providing and fixing pre cast solid concrete kerb stones of size 450x200x400 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete., complete.	No's	1721.00	477.00	Rupees Four Hundred Seventy Seven Only
10	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.	Sqm	309.76	39.22	Rupees Thirty Nine And Paise Twenty Two Only
11	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications	Sqm	309.76	84.80	Rupees Eighty Four And Paise Eighty Only

Signature Of The Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Yelahanka Division